

Reference No.: **NPP-192-REV1**

Tuesday, 30 June 2026

To: **TRICLOVER LIMITED**

Dear Sir/Madam,

QUOTATION FOR SUPPLY ONLY OF LV SWITCHBOARDS

We thank you for your enquiry for the above project, and are pleased to quote as follows: -

Annexure 1: Notes/ Comments on Our Offer

Annexure 2: Commercial Terms (Schedule of Prices)

Annexure 3: Specific Terms & Conditions

Annexure 4: Detailed Technical Offer & Data Sheets

We trust that you will find our offer in line with your requirements and should you require any further information, please do not hesitate to contact the undersigned.

We trust this meets with your requirements.

Yours Faithfully,

Karen Jillo

npsladmin@neiltd.com

Nationwide Power Systems Ltd.



ANNEXURE I: NOTES/ COMMENTS ON OUR OFFER

a) For the MAIN LV SWITCHBOARDS;

a) We have offered Free Standing Electro-Statically powder coated **Form 3B, IP31** LV BOARD with **Front Access, Bottom** cable entry and exit.

b) We have offered SIEMENS ELECTRIC Switchgear.

c) Our offer is for supply only (Ex-Works Nairobi) and does not include site delivery, assembly, testing and commissioning.

ANNEXURE II: (COMMERCIAL TERMS)

1.LV BOARDS PRICE SCHEDULE

ITEM NO	DESCRIPTION	UOM	QTY	UNIT PRICE(IN KSH.)	TOTAL(IN KSH.)
1	1600A MAIN LV BOARD	PC	1	5,784,800.00	5,784,800.00
Sub total Amount in KSH, Ex-works, Nairobi (subject to VAT)					5,784,800.00
16% VAT-IN KSH.					925,568.00
Total Amount in KSH, Ex-works, Nairobi (Inclusive of VAT)					6,710,368.00

ANNEXURE III: SPECIFIC TERMS & CONDITIONS

1. SCOPE OF SUPPLY

- Our offer is for supply only and does not include **site delivery, assembly, testing and commissioning.**

2. VALIDITY PERIOD

- This offer is open for acceptance for **30** days from the date hereof: thereafter subject to confirmation.

3. TERMS OF PAYMENT

- 50% advance with order.
- 50% before collection or within 30 days of notification that goods are ready for collection.

4. DELIVERY TERMS

- (Ex-Works Nairobi)

5. DELIVERY TIMELINES

- To be Confirmed after Order Confirmation (TBA)

ANNEXURE IV: DETAILED TECHNICAL OFFER.

1.LV BOARD TECHNICAL DETAILS

SR. NO	PARTICULAR	TECHNICAL DESCRIPTION LV SWITCHGEARS	QTY
1)	MAIN LV BOARD- OPTION 1	This will be a free-standing, electrostatically powder-coated Form 3B LV board, IP31, with front and rear Access, bottom cable entry. Built to IEC 61439-1 & 2 standards, KEBS certified, and compliant with ISO 9001 (Quality), ISO 14001 (Environmental), ISO 45001 (Health & Safety), and full EHS requirements and will consist of the following: a) INCOMING CHANGEOVER SECTION COMPRISING OF; - 1 No. 1600A FP ACB mechanically and electrically interlocked. (KPLC). 2 No. 800A FP ACB mechanically and electrically interlocked. (GEN). 2 No. Synchro Check relays. - A Set of current transformers. - Controls and wiring - Set of suitably rated TPN Busbar. 3 Set. Indicator Lamps with Protection MCBs. - Set of Mains/ GEN on -Load Indicators 3 No. Multifunction Meter. 3 Set CTs and protection for above meter. b) INCOMING SOLAR SECTION COMPRISING OF; - 1 No. 1600A FP 55KA manual ACB. 1 Set. Indicator Lamps with Protection MCBs. c) OUTGOERS COMPRISING OF; - 1 No. 630A TP MCCB adj 36KA. 3 No. 400A TP MCCB adj 36KA. 5 No. 250A TP MCCB adj 25KA. 1 No. 200A TP MCCB adj 25KA.	1

		• 3 No. 160A TP MCCB adj 25KA. • 3 No. 125A TP MCCB adj 25KA. 400KVAR APFC COMPRISING OF; - • 1 No. 800A TP ACB. • 1 No. APFC controller. • 1 No. 1600/5A CT. • Set of suitable sized Fuses. • Capacitor Duty contactors and Capacitors for PFC Bank. • 1 Set Fan and Louvre. Proposed Enclosure: 2100(H)3500(W)X800(D)MM Proposed Enclosure: 2100(H)800(W)X800(D)MM	
--	--	--	--